# Presentation to Lake Erie Allegany Partnership 18 March 2015



### Outline

- Engineering With Nature
- GLRI Green Breakwaters Projects
  - ► Cleveland Harbor Pilot Project
  - ► Ashtabula Harbor Pilot Project




## Engineering With Nature...

...the intentional alignment of natural and engineering processes to efficiently and sustainably deliver economic, environmental and social benefits through collaborative processes.

#### **Key Elements:**

- Science and engineering that produces operational efficiencies
- Using natural process to maximum benefit
- Broaden and extend the benefits provided by projects
- Science-based collaborative processes to organize and focus interests, stakeholders, and partners












### **GLRI Green Breakwaters**

- EPA funded pilot projects demonstrating the potential to economically incorporate aquatic habitat features into the O&M repairs of Federal Navigation Structures, and to provide nesting habitat for targeted bird species on top of existing breakwater structures.
- EPA funding covered the differential cost of including the habitat features into the existing O&M repair projects
- Cleveland Harbor Aquatic habitat only
- Ashtabula harbor Aquatic habitat, common tern nesting area, low growing vegetation habitat



### **Great Lakes Navigation System (GLNS)**





# Are there ways to improve biological value of blocks?








## **Texture Scale**











## Cleveland Project Schedule

- April/May 2012 13 toe blocks installed
- October 2012 sampling
- April/May 2013 3 of the 2012 blocks reset Hurricane Sandy repairs – no new toe blocks
- June 2013 sampling
- October 2013 sampling
- April/May 2014 remaining 21 blocks set
- 2014/15 data analysis & reporting



## Toe Block Layout

S D C S D G S C S G

- S Shelf (5)
- D Dimple (2)
- C Control (3)
- G Groove (3)

- A total of 34 blocks were set
- 2013 work was delayed due to necessary Hurricane Sandy repairs









# Sampling Grid

Top row was not submerged








Representative Samples Control Grooved **Grooved Shelf Dimpled** 

#### Preliminary Results – Abundance – October 2012




## **Preliminary Conclusions**

- Initial colonization greater for most groups on grooved blocks
  - ► Invertebrate Secondary Production Increase
- Potential to provide juvenile fish refuge









## East Breakwater



## Ashtabula Project Schedule


- Phase I Construction (2013)
  - Aquatic habitat block installation
  - 250 sq ft of tern nesting habitat
- Phase II Construction (2014)
  - Aquatic and low growth vegetation habitat block installation
  - Additional 250 sq ft of tern nesting habitat
- Phase III Construction (2015 Planned)
  - Complete installation of habitat blocks
- Monitoring
  - Planned monitoring period 2014-2017
  - No terns yet
  - Aquatic and low growth vegetation monitoring starting in 2015
- O&M of Tern Habitat
  - By The Nature Conservancy once USACE study is completed

# Tern Nesting Habitat New York Power Authority – Buffalo, NY




See http://niagara.nypa.gov/EcologicalStandingCommittee/EcoStanddefault.htm

## Ashtabula, OH Tern Nesting Blocks












## Phase II Tern Habitat













# CERTIFICATE OF RECOGNITION

PIANC, the World Association for Waterborne Transport Infrastructure.

hereby grants the company  US ACE	
the "Certificate of Recognition" for the project	
(name) "Cleveland	ARROW head BREakwater"
(place/country)	d States
developed following the "Working with Nature" philosophy as approved by the jury.	
Brussels, Octobel 8, 2013 (date)	
Louis Van Schel	6. Caur- Geoffroy Caude

Secretary-General



President

# The USACE Team

- Tom Fredette (ERDC-EL)
- Tony Friona (ERDC-EL)
- Paul Bijhouwer (LRB)
- Burton Suedel (ERDC-EL)
- •Rich Ruby (LRB)
- Cynthia Banks (ERDC-EL)
- Joan Clarke (ERDC-EL)
- Cheryl Pollock (ERDC-CHL)



### **Questions?**



